



Traffic Striping, Markings and Legends

The work under this section shall cover the striping of all streets and parking lots as indicated on the construction plans. The work shall include the layout of all parking spaces, legends, markings and roadway stripe.

Alabama Department of Transportation Standard Specifications for Highway Construction, latest edition.

The Contractor shall allow newly placed bituminous concrete plant mix to cure for fourteen (14) days prior to any application of traffic stripe unless approved by owner or engineer.

Cleaning of pavement shall be in accordance with Section 701.03(b) of the Alabama Department of Transportation Standard Specifications for Highway Construction, latest edition.

The Contractor shall be required to prepare site for striping purpose. The work shall include but not limited to sweeping of pavement and removal of grass from top of curbs prior to paint application.

CONSTRUCTION STAKING

Layout of parking will be the same as that shown on plans. The Contractor will be responsible for parking layout.

MATERIALS

All striping, arrows, legends, markings, etc. shall conform to Section 856.02 of the Alabama Department of Transportation Standard Specifications for Highway Construction, latest edition.